

RUPSHA POWER SYSTEMS LTD.

House 22, Road 7, Sector 4, Uttara, Dhaka 1230 · Dummy vendor created for the IUT alumni AI Session

Quotation No: RPS/Q/26/0917 **Date:** 18 September 2026

To: Procurement, Meghna Knit Composite Ltd., Konabari, Gazipur

Ref: Your RFQ/ENG/2026/118 — 500 kVA packaged substation

Dear Sir,

We are pleased to offer the following against your RFQ.

Item	Description	Amount (BDT)
1	500 kVA 11/0.415 kV Dyn11 ONAN transformer, copper winding, OCTC $\pm 2 \times 2.5\%$, IEC 60076	48,50,000
2	11 kV VCB 630 A, 20 kA/3 s, numerical relay (O/C + E/F)	21,00,000
3	LT panel: 1000 A ACB incomer, 6 MCCB outgoing (2x400 A, 4x250 A), MFM	17,80,000
4	300 kVAR automatic PFI panel, 6 steps, standard capacitors	9,20,000
5	Outdoor IP54 enclosure, installation, earthing, testing & commissioning	15,50,000
	Total (excluding VAT & AIT)	1,11,00,000

Guaranteed losses: no-load 820 W; load loss at 75 °C 5,650 W.

Delivery: 14 weeks from work order. **Warranty:** 18 months from delivery.

Service: our service centre at Tongi, Gazipur; 24-hour response.

Type tests: transformer and VCB type test reports (CPRI, 2019) attached.

Authorisation: manufacturer's authorisation letters attached.

Validity: 90 days. **Payment:** as per RFQ. **LD:** accepted as per RFQ.

Earthing will be done as per standard practice.

Yours faithfully,

Engr. M. Hasan, Sales Manager